



भा.कृ.अनु.प.–केन्द्रीय कृषि अभियांत्रिकी संस्थान
नबीबाग, बैरसियारोड, भोपाल-462 038

ICAR-Central Institute of Agricultural Engineering

NabiBagh, Berasia, Road, Bhopal- 462 038 (M.P.)

Tel. 0755-2521021 Fax No. 0755-2734016, Website:- <http://www.ciae.nic.in>



By Speed Post

F.No.: CIAE/EMS/Works /2023-24/

Dated: 26.02.2024

To,

Sub: Repairing of flooring of E-3 Quarter at CIAE Campus, Bhopal-reg.

Dear Sirs,

On behalf of the Director, CIAE, Bhopal, I am to invite your lowest quotation for **"Repairing of flooring of E-3 Quarter at CIAE Campus, Bhopal"** from the civil/electrical contractors on **limited tender enquiry** as per the approved the list (registered with **CPWD, State PWD or any other Govt.** agency at ICAR-CIAE, Bhopal) following terms & conditions.

1. The rates should be submitted on the prescribed schedule of work and notified in the Annexure-1 and the contractor should sign it. **Taxes, if any, must be quoted, separately otherwise, it will be assumed that the rates are inclusive of all taxes, etc.**
2. No over writing in the offer is permitted. However correction it any must be signed by the contractor.
3. Quotation must be sent in a sealed cover envelope mentioning **"Repairing of flooring of E-3 Quarter at CIAE Campus, Bhopal"**.
4. Quotations must be sent through Registered Post/Post/Speed Post/Couriers to the **In-Charge Estate Management Section, ICAR-Central Institute of Agricultural Engineering, Nabi Bagh, Berasia Road, Bhopal-462 038. No quotation will be accepted by hand.**
5. **The quotation must be attached with documents like valid PAN, GSTN, Registration Certificate with CPWD, State PWD or any other approved government agency with authorized signature and seal of the agency and the same must be received before the time and date mentioned in the notice inviting quotation i.e. 04.03.2024.**
6. Director, CIAE, Bhopal has every right to extend the date of submitting the quotation.
7. Any quotation received after the date of submission mentioned in the notice of inviting quotation shall be rejected and returned unopened to the quote/contractor.
8. The contractor shall be entirely responsible for the security and safety of persons employed by him.
9. During the work, the contractor shall be responsible for any loss caused by its worker and shall be recovered from the bill.
10. The payment will be made within reasonable time say 30 days after completion of work. No part payment will be made to the contractor. Since the mode of payment will be e-payment system, hence bank account Number and name of the Bank with location and IFSC code No. of Bank may be mentioned in the quotation positively.
11. The Director, CIAE, has the right to cancel awarded work if the contractor fails to perform jobs specified in the work order.
12. Bidders have to sign a Bid securing declaration as per Rule 170 of GFR 2017 and order of Ministry of Finance OM No F 9/4/2020 PPD dated 12.11.2020.

Bid Security Certificate: - I/We hereby accept that I/We will not withdraw or modify Bid furnished during period of validity of the Limited Tender for **"Repairing of flooring of E-3 Quarter at CIAE Campus, Bhopal"**.

(Signature & Seal)

For M/s _____

13. Within 07 (Seven) days after the issue of notification of award (i.e. work order) by the contractor, the successful bidder is required to submit 5% performance security of the value of contract/order in the form of account payee DD in favour of ICAR Unit CIAE, Bhopal from a commercial issued Bank, as per Rule 171 of GFR 2017 and order of Ministry of Finance OM No. F9/4/2020-PPD dated 12.11.2020.
14. Payment of bill will be made only after successful completion of the work and satisfactory test report.
15. If the contractor does not care to improve its performance in a reasonable time in spite of written/verbal instruction and warning. The decision of the Director, CIAE shall be final.
16. If any interpretation of rules/provision arises, the decision of the Director, CIAE is final and shall be bound to accept by the contractor.
17. Director, CIAE reserves every right to accept or reject the quotation without any reasons thereof.
18. The work should be carried out as per CPWD specification as per Annexure-I
19. All dispute subject to Bhopal jurisdiction only.
20. All communications must be addressed to the undersigned by Designation only and not by name.
21. All the tools required for completion of work will be arranged by the contractor.
22. TDS will be deducted as per rules.
23. Loss and/or damages. In case of any loss or damage done to the property of the Institute and Krishi yantra Colony by the personnel provided to the Institute by the Contractor for labour service contract for civil work at this Institute, the full damages will be recovered from the contractor.
24. The labour contractor agrees to discharges their entire legal as well as other obligation in respect of their employees in respect of their wages and other service conditions and shall also comply with all the rules and regulations and provision of law in force that may be applicable to them from time to time. Statutory obligations under contract labour (Regulation and Abolition Act), 1970, Workmen's Compensation Act. EPF and MP Act. Industrial Dispute Act etc. The Labour contractor agrees to indemnify and keep indemnified the Institute from any claims loss or damages that may be used to the institute on account of the labour contractor failure to comply with their obligations under the various law towards their staff/employees by them for any loss or damage to the institute due to acts/omissions of the contractor.
25. The contractor shall be responsible to give the minimum wages to the laborers as per the Govt rate as amended from time to time including all other fringe benefits as per labour laws of Govt of India. It is amply and mutually agreed that the institute shall not be responsible for any welfare measures benefits etc to the laborers and that the institute shall not be responsible for any untoward incident/casually of the laborers during their engagement in the activities work.
26. Institute will not responsible for unloading, handling, storing staking of the material at site.

Your faithfully,


I/c, Estate Management section

Copy to:

1. Chairman, IWC for kind information please.
2. AAO (P-II) for publishing the limited tender in CPP Portal.
3. In-charge, AKMU for uploading in CIAE Website, with soft copy.
4. PS to CAO for kind information of the CAO, ICAR-CIAE, Bhopal please.
5. Notice board
6. Guard file

Repairing of flooring of E-3 Quarter at CIAE Campus, Bhopal

S.no	Item	Unit	Quantity	Rate	Amount
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	sqm	85		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	7.5		
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	7.5		
4	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm .	sqm	85		
5	Providing filling compaction of copra under floor .	cum	22.5		
6	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil .	cum	22.5		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	650.00		
8	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) kg	kg	110		
9	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	kg	130		
10	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminum snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	sqm	25		
11	Filling the gap in between aluminum frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete. Upto 5mm depth and 5 mm width	meter	50		
				Total Rs.	

Ayaz