



ICAR - CENTRAL INSTITUTE OF AGRICULTURAL ENGINEERING

REGIONAL STATION, COIMBATORE – 641007 (TAMILNADU)

Tele- 0422-2472623, email: ciaerccbe@gmail.com



No. CIAE-RS/3-3(E)/2024-25

Dated: 28.08.2024

To

M/s.

Sub: Quotation for providing paver blocks and ramp for existing vehicle parking shed (staff and visitors) – size: 60ft. x22ft. at ICAR- CIAE, RS Coimbatore – reg.


Dear Sirs,

On behalf of the Director, ICAR- CIAE, Bhopal, I am to invite your lowest quotation for **"providing paver blocks and ramp for existing vehicle parking shed (staff and visitors) – size: 60ft. x22ft. at ICAR- CIAE, RS Coimbatore"** from the civil contractors as per enclosed **Annexure-I** on following terms & conditions.

1. The rates should be submitted on the prescribed schedule of work and notified in the **Annexure-I** and the contractor should sign it. **Taxes, if any, must be quoted, separately otherwise, it will be assumed that the rates are inclusive of all taxes, etc.**
2. No over writing in the offer is permitted. However, correction if any must be signed by the contractor.
3. Quotation must be sent in a sealed cover envelope mentioning **"Quotation for providing paver blocks and ramp for existing vehicle parking shed (staff and visitors) – size: 60ft. x22ft. at ICAR- CIAE, RS Coimbatore"**.
4. Quotations must be sent through Registered Post/Post/Speed Post/Couriers to the **Head(I/c) ICAR-Central Institute of Agricultural Engineering, Regional Station, Veerakeralam Road, Sugarcane Breeding Institute Post, Coimbatore-641 007 due on 18.09.2024 05.00 PM.**
5. **No quotation will be accepted by hand.**
6. Director, ICAR-CIAE, Bhopal has every right to extend the date of submitting the quotation.
7. Any quotation received after the date of submission mentioned in the notice of inviting quotation shall be rejected and returned unopened to the quote/contractor.
8. The contractor shall be entirely responsible for the security and safety of persons, employed by him.
9. During the work, the contractor shall be responsible for any loss caused by its worker and shall be recovered from the bill.
10. The payment will be made within reasonable time say 30 days after completion of work. No part payment will be made to the contractor. Since the mode of payment will be e-payment system, hence bank account No. and name of the Bank with location and IFSC code No. of Bank may be mentioned in the quotation positively.
11. The Director, ICAR-CIAE, has the right to cancel awarded work if the contractor fails to perform jobs specified in the work order.

12. If the contractor does not care to improve its performance in a reasonable time in spite of written/verbal instruction and warning. The decision of the Director, ICAR-CIAE shall be final.
13. If any interpretation of rules/provision arises, the decision of the Director, ICAR-CIAE is final and shall be bound to accept by the contractor.
14. Director, ICAR-CIAE reserves every right to accept or reject the quotation without any reasons thereof.
15. The work should be carried out as per specification as per Annexure-I
16. All dispute subject to Bhopal Jurisdiction only.
17. All communications must be addressed to the undersigned by Designation only and not by name.
18. All the tools required for completion of work will be arranged by the contractor.
19. TDS will be deducted as per rules.
20. Loss and/ or damages: - In case of any loss or damage done to the property of the Institute and Krishyantra Colony by the personnel provided to the Institute by the Contractor for labour service contract for civil work at this Institute, the full damages will be recovered from the contractor.
21. The labour contractor agrees to discharges their entire legal as well as other obligation in respect of their employees in respect of their wages and other service conditions and shall also comply with all the rules and regulations and provision of law in force that may be applicable to them from time to time. Statutory obligations under contract labour (Regulation and Abolition Act), 1970, Workmen's Compensation Act, EPF and MP Act, Industrial Dispute Act etc. The Labour contractor agrees to indemnify and keep indemnified the Institute from any claims, loss or damages that may be caused to the institute on account of the labour contractor failure to comply with their obligations under the various law towards their staff/employees by them for any loss or damage to the institute due to acts/ omissions of the contractor.
22. The contractor shall be responsible to give the minimum wages to the laborers as per the Govt. rate as amended from time to time including all other fringe benefits as per labour laws of Govt. of India. It is amply and mutually agreed that the institute shall not be responsible for any welfare measures benefits etc to the laborers and that the institute shall not be responsible for any untoward incident/casually of the laborers during their engagement in the activities work.
23. Institute will not responsible for unloading, handling, storing, staking of the material at site.

Encl: Annexure-I


28/8/2024

Yours faithfully,
(Head(I/c), ICAR-CIAE RS, Coimbatore)

Head / प्रभारी

REGIONAL STATION

ICAR-CENTRAL INSTITUTE OF AGRICULTURAL ENGINEERING
Coimbatore - 641 007.

क्षेत्रीय केन्द्र

भा कृ अ प - केन्द्रीय कृषि अभियांत्रिकी संस्थान
कोयंबटूर - ६४१ ००७.

Copy to:

1. Chief Admn. Officer, ICAR-CIAE, Bhopal – 38
2. Sr.Finance & Accounts Officer, ICAR-CIAE, Bhopal – 38
3. Asst.Admn. Officer (P-II), ICAR-CIAE, Bhopal – 38
4. I/c, AKMU Cell for placing in the Institute web portal for wide publicity.
5. PS to Director, ICAR-CIAE, Bhopal – 38 for kind information to the Director, ICAR-CIAE
6. Guard File

Annexure- I

Name of work: Providing paver blocks and ramp for existing vehicle parking shed (staff and visitors) – size: 60ft. x22ft. at ICAR- CIAE, RS Coimbatore

Item No.	Item of Work	Qty.	Unit Rate Rs.	Amount, Rs
	Providing paver blocks with ramp for existing vehicle parking shed (staff and visitors) – size: 60ft. x22ft.			
1	Providing and laying in position cement concrete of specified grade excluding the cost centering and shuttering -All work up to plinth level			
1.1	1:1.5:3 (1 Cement: 1.5 Coarse sand : 3 graded stone aggregate 20mm nominal size)	2.0 cum		
1.2	1:5:10 (1 Cement: 1.5 Coarse sand : 10 graded stone aggregate 40 mm nominal size)	12.0 cum		
2	Brick work with non-modular fly ash bricks conforming to IS: 12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in:			
2.1	Cement mortar 1:6 (1 Cement : 6 Course sand)	2.50 cum		
3	15 mm cement plaster on the rough side of single or half brick wall of mix:			
3.1	1:6 (1 Cement : 6 fine sand)	4.0 Sqm		
4	Providing and fixing precoated galvanized steel sheet, roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer, on both microns using self-drilling/self-tapping screws complete:			
4.1	Flashing /Aprons. (Up to 600mm)	20.0 meter		
5	Providing and laying factory made chamfered edge Cement Concrete paver block in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thickness compacted bed of sand, compacting and proper embedding /laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand.			
5.1	60mm thick C.C paver block of M-35 grade with approved colour design and pattern	130 Sqm		
	Sub Total			
	GST @			
	Total			

(Rupees in words

)

Seal & Signature of the Firm