



भा.कृ.अनु.प.-केन्द्रीय कृषि अभियांत्रिकी संस्थान
नबीबाग, बैरसियारोड, भोपाल-462 038

ICAR-Central Institute of Agricultural Engineering
Nabi Bagh, Berasia, Road, Bhopal- 462 038 (M.P.)

Tel. 0755-2521021 Fax No. 0755-2734016, Website:- <http://www.ciae.nic.in>



By Speed Post

Dated: 24.01.2025

F.No.: CIAE/EMS/WS-125/2024-25/1413

To,

Sub: "Repair of vitrified tiles flooring in the rooms of IDED and UAE and other minor works"-reg.

Dear Sirs,

On behalf of the Director, CIAE, Bhopal, I am to invite your lowest quotation for **"Repair of vitrified tiles flooring in the rooms of IDED and UAE and other minor works"** from the civil/electrical contractors on **limited tender enquiry** as per the approved the list (registered with **CPWD, State PWD or any other Govt.** agency at ICAR-CIAE, Bhopal) following terms & conditions.

1. The rates should be submitted on the prescribed schedule of work and notified in the Annexure-1 and the contractor should sign it. **Taxes, if any, must be quoted, separately otherwise, it will be assumed that the rates are inclusive of all taxes, etc.**
2. No over writing in the offer is permitted. However correction if any must be signed by the contractor. In case of non-conformalities for the quoted rates between figures and words or sub totals etc.; the rules vide section 7.3.2 of manual of procurement of goods 2017 (G01). Shall be adopted.
3. Quotation must be sent in a sealed cover envelope mentioning **"Repair of vitrified tiles flooring in the rooms of IDED and UAE and other minor works"**.
4. Quotations must be sent through Registered Post/Post/Speed Post/Couriers to the **In-Charge Estate Management Section, ICAR-Central Institute of Agricultural Engineering, Nabi Bagh, Berasia Road, Bhopal-462 038. Quotation will NOT be accepted by hand.**
5. The quotation must be received before 15 days time from the date mentioned in the notice inviting quotation i.e. 10.02.2025.
6. The contractors who have already submitted documents like valid PAN, GSTN, Registration Certificate with CPWD, State PWD or any other approved government agency with authorized signature and seal of the agency on previous occasions to our Institute then such documents may not be required to be re-submitted again . In this condition only bid rate document properly filled may be enclosed.
7. Director, CIAE, Bhopal has every right to extend the date of submitting the quotation.
8. Any quotation received after the date of submission mentioned in the notice of inviting quotation shall be rejected and returned unopened to the quote/contractor.
9. The contractor shall be entirely responsible for the security and safety of persons employed by him at the cite or premises.
10. During the work, the contractor shall be responsible for any loss caused by its worker to the Institute and shall be recovered from the bill.
11. The payment will be made within reasonable time say 30 days after completion of work. No part payment will be made to the contractor. Since the mode of payment will be e-payment system, hence bank account Number and name of the Bank with location and IFSC code No. of Bank may be mentioned in the quotation positively.
12. The Director, CIAE, has the right to cancel awarded work if the contractor fails to perform jobs specified in the work order.
13. Bidders have to sign a Bid securing declaration as per Rule 170 of GFR 2017 and order of Ministry of Finance OM No F 9/4/2020 PPD dated 12.11.2020.

Bid Security Certificate: - I/We hereby accept that I/We will not withdraw or modify Bid furnished during period of validity of the Limited Tender for **"Repair of vitrified tiles flooring in the rooms of IDED and UAE and other minor works"**.

(Signature & Seal)

For M/s _____

14. Within 09 (Nine) days after the issue of notification of award (i.e. work order) by the contractor, the successful bidder is required to submit 5% performance security of the value of contract/order in the form of account payee DD in favour of ICAR Unit CIAE, Bhopal from a commercial issued Bank, as per Rule 171 of GFR 2017 and order of Ministry of Finance OM No. F9/4/2020-PPD dated 12.11.2020.
15. Payment of bill will be made only after successful completion of the work and satisfactory test report.
16. If the contractor does not care to improve its performance in a reasonable time in spite of written/verbal instruction and warning. The decision of the Director, CIAE shall be final. If the contractor fails to execute /start the work after the issue of work order, Director CIAE reserve the rights to debar the firm from enplanement.
17. If any interpretation of rules/provision arises, the decision of the Director, CIAE is final and shall be bound to accept by the contractor.
18. Director, CIAE reserves every right to accept or reject the quotation without any reasons thereof.
19. The work should be carried out as per CPWD specification as per Annexure-I
20. All dispute subject to Bhopal jurisdiction only.
21. All communications must be addressed to the undersigned by Designation only and not by name.
22. All the tools required for completion of work will be arranged by the contractor.
23. TDS will be deducted as per rules.
24. Loss and/or damages. In case of any loss or damage done to the property of the Institute and Krishi yantra Colony by the personnel provided to the Institute by the Contractor for labour service contract for civil work at this Institute, the full damages will be recovered from the contractor.
25. The labour contractor agrees to discharges their entire legal as well as other obligation in respect of their employees in respect of their wages and other service conditions and shall also comply with all the rules and regulations and provision of law in force that may be applicable to them from time to time. Statutory obligations under contract labour (Regulation and Abolition Act), 1970, Workmen's Compensation Act. EPF and MP Act. Industrial Dispute Act etc. The Labour contractor agrees to indemnify and keep indemnified the Institute from any claims loss or damages that may be used to the institute on account of the labour contractor failure to comply with their obligations under the various law towards their staff/employees by them for any loss or damage to the institute due to acts/omissions of the contractor.
26. The contractor shall be responsible to give the minimum wages to the laborers as per the Govt rate as amended from time to time including all other fringe benefits as per labour laws of Govt of India. It is amply and mutually agreed that the institute shall not be responsible for any welfare measures benefits etc to the laborers and that the institute shall not be responsible for any untoward incident/casually of the laborers during their engagement in the activities work.
27. Institute will not responsible for unloading, handling, storing staking of the material at site.
28. The contractors shall produce a self declaration for non-black listing/suspension for the agency as per the enclosed in Annexure-II.

Your faithfully,


I/c, Estate Management section

Copy to:

1. Chairman, IWC for kind information please.
2. AAO (P-II) for publishing the limited tender in CPP Portal.
3. In-charge, AKMU for uploading in CIAE Website, with soft copy.
4. PS to CAO for kind information of the CAO, ICAR-CIAE, Bhopal please.
5. Guard file.

Repair of vitrified tiles flooring in the rooms of IDED and UAE and other minor works

S.N.	Item	Qty	Unit	Rate	Amount
Site 1 : Providing & fixing vitrified tiles flooring in the rooms of IDED and Adjacent MIS hall of head IDED					
1.	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only .Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.Double charge vitrified tile polished finish of sizeSize of Tile 600 x 600 mm.	195	sqm		
2.	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	40	Sqm		
3.	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	110	sqm		
4.	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	25	sqm		
5.	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door width upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	11	each		
6.	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.Twin rubber stopper	11	each		
7.	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats	830	sqm		
8.	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	830	sqm		
9.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	180	sqm		
Site : 02 Repair & Maintenance work to be carried out in the AICRP on UAE					
10.	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33 mm thick (galvanized @ 120 grams per sqm including both	26	sqm		

	sides)comprising of main-T runners of size 24x38 mm of length 3000 mm,cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to formgrid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directions of the Engineer-in- Charge With 15 mm thick Tegular edged light weight calcium slicate false ceiling tiles with 6 nos. of 600x600 mm LED surface lights				
11.	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only .Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.Double charge vitrified tile polished finish of sizeSize of Tile 600 x 600 mm.	40	sqm		
12.	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	10	sqm		
13.	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	10	sqm		
14.	Dismantling tile work in floors and roofs/walls laid in cement mortar, cement including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm.	10	sqm		
15.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, itred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings	30	kg		

	and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)				
16.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	40	kg		
17.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	8	sqm		
18.	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats	200	Sqm		
19.	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	200	Sqm		
20.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	50	sqm		
				Total Rs.	

Agarwal

PART - V

LIST OF APPROVED MATERIALS (CIVIL)

Note :

1. Unless otherwise specified, the brand/make of the material as specified in the item nomenclature or in the particular specifications or in the list of approved materials attached in the tender, shall be used in the work.
2. The Contractor shall obtain prior approval from the Engineer-in-charge before placing order for any specific material/ Brand/ Make.
3. Whenever the specified brand of material is not available than, the Engineer-in-charge may approve any material equivalent to that specified subject to proof being offered by the Contractor for its equivalence and its non-availability to his satisfaction.
4. If any brand which have been approved by the Director, CIAE till the date of last date of submission of respective tender shall be deemed as approved brand even if it has not been mentioned in approved brand or make in the NIT.

MATERIALS:

BRAND/MAKE

1.	AAC Block	Aerocon, Ultratech, Ecolite, Concretite, BILTECH, Dlite Blocks, Orillite – Kota, E-Crete
2.	AAC Block Adhesive	Ferrous crete(Ferro-1188), ARDEX ENDURA (White Star), Ultratech (Fixo-Block), Berger Home Shield
3.	(a) Acrylic Exterior paint	Apex Ultima of Asian Paints, Weather Coat all Guard of Berger, Weather Shield Max of Dulux
	(b) Acrylic Emulsion paint	Royal Luxury Emulsion of Asian Paints, Silk Luxury emulsion of Berger Paint, Velvet touch emulsion of Dulux.
	(c) Acrylic Distemper	Royal Luxury Emulsion of Asian Paints, Silk Luxury emulsion of Berger Paint, Velvet touch emulsion of Dulux.
	(d) Synthetic Enamel Paint	Apcolite of Asian Paint, Luxol of Burger Paint and Dulux Paint.
4.	Epoxy Adhesive	FOSROC, Aquomix , Choksey, BAL-ENDURA, Berger Paints India Ltd.
5.	Aluminium Composite Panel	Alpolic, Aluco Bond, Reynobond, Euro bond, Alstrong, Aludecor.
6.	Aluminum Door window hardware (ISI Mark only)	Shalimar, Archie, Classic(ISI)
7.	Aluminium Extrusions / sections	Hindalco, Indian Aluminium Co., Jindal
8.	Annealed Float Glass	Saint Gobain, Modi Guard, Asahi
9.	Auditorium Chairs/ Furniture	Godrej, Wipro, Methodex, Bonton, Penworker, Durian, Harman Miller, Featherlite, Haworth & Geeken
10.	Bitumen	Indian Oil, Hindustan Petroleum, Bharat Petroleum
11.	Calcium Silicate Board / Tiles	Aerolite, Hilux, Starpan
12.	CC Pavers / Grass Pavers*	Nitco, Ultra, KJS Concrete, Duracrete, Mehtab Tiles, Kaptim, Khalsa, Dalal
13.	Centrifugally Cast Iron Pipe & Fittings	NECO, SKF, BIC, RIF, KAPILANSH, HIF, Electrosteel,
14.	C.I. Hubless pipe	SKF, NECO, Kapilansh
15.	Ceramic Tiles	Kajaria, Somany, Nitco, Johnson, RAK Ceramics
16.	Chequered	Dura, Eurocon, Modern, Hindustan, Johnson, NITCO
17.	CI Manhole Cover	SKF, NICO, Hepco, Kapilansh
18.	CI Double flanged non-return valves	Kirloskar, Sant, Kartar
19.	CI / SCI Spun pipes and fittings	NECO, HEPCO, Bengal Iron Corporation, Kapilansh
20.	Cover Block	Khalsa, Balaji, Simcom
21.	CP fittings	Jaquar, Marc, Kohler, Hindware , Shakti, Prayag Polymers(P), Ltd.
22.	CPVC Pipes & Fittings	Astral , Ashirvad, Prince, Supreme, Finolex, VECTUS , Prayag
23.	CRCA Steel sheet	TATA, Jindal, Sail
24.	Curtain Carrier / Drapery Rod	Marvel, Vista levlor, Johnson.
25.	Dash fastener, Expansion Bolt	Hilti, Bosch, Fischer
26.	Hydraulic Door closer, Floor springs	Dorma, Hettich, Hafele, dorset, Hardwin, kelvin, Godrej
27.	Ductile Iron Pipe (Water Supply)	Electro steel, Kesoram, Electro Spun, TATA DUCTURA, Swastic
28.	EPDM Gasket	Hanu, Anand, Lescuyer
29.	GRC	Unistone, Dalal, Swastic
30.	Epoxy Grouting Compound	Pidilite, Ferrous Crete(Ferro-102), MYK- LATICRETE, Berger Paints India Ltd., Ultratech
31.	Epoxy Primer & Paints	Berger, Pidilite, CICO, BASF, SIKA, Asian Paints
32.	Elastomeric Antifungal Exterior Paint	Ultima of Asian Paints, Weathershield of ICI Dulux, Alguard of Berger
33.	Fire Check door	Navair, Godrej, Shakti
34.	Float Glass Mirror	Modifloat, Saint Gobain, Asahi, TATA float
35.	Flush Doors (ISI Mark only)	Century, Archid, Greenply, Marino, Duro, Jayna, Gujcon, Durian, A1 flush door, M.P. Wood
36.	Friction Stay	Albihari, Geze, Hettich, Securistyle, Ebco
37.	Galvanized/Stainless Steel Anchor Fasteners	Shakti, Arrow, Hilti, Fischer
38.	GI Pipe & fittings	Tata, Zenith, Jindal, Prakash Surya, Swastik
39.	GI Sheet	Sail, TATA, Jindal, National, Bhushan
40.	Geotextile	Manas, Osian, Wadhwa
41.	Gun Metal Gate Valve , Ball valve	Zoloto, Leader, SANT
42.	Glass Mosaic Tile	Bisazza, Italia, Palladio, Mridul
43.	Gypsum Board (False Ceiling)	Boral Gypsum, India Gypsum, Saint- Gobain
44.	Gypsum Plaster	Asian Paints, Fosroc, BASF, Sika, Saint-Gobain, Pidilite
45.	FRP Door	Fiberways, Jayna, Shiv Shakti

46.	Hardener	Hardcrete of Snowcem India, Pidilite, CICO., Berger Paints India Ltd.
47.	HDPE Pipes	VECTUS, Emco, Polyfins, Pioneer, Plyfab, Jain Irrigation, Kissan
48.	Jet Assembly for EWC/Health Faucet	Parryware , Jaquar, Marc, Hindware
49.	Kitchen loft tank	Sintex, Tirupati Structural Ltd, KMS Plast world P.Ltd. Planet Plastics, Sri Kamakshi Traders, Sreyah Novel InC.
50.	Kerb Stone	Mehtab, Hindustan, Concreto, Kaptim, K.K., Khalsa
51.	Laminate and Veneers	Merino, Greenlam, Formica, Kitlam, Durian
52.	Locks / Latch	Godrej, Harrision, Dorma, Yale, dorset, Hafele
53.	Marine Plywood / BWP Ply/Plywood	Duro, Century, Kitply, Greenply, Archidply
54.	Melamine Polish	Asian Paints, Pidilite, ICI Dulux, Berger
55.	Metal False Ceiling	Nitobond, Armstrong, Trac, Durlum, Lafarge, Anutone, Hunter Douglas, Hi-steel
56.	Mineral Fibre/ GRG Ceiling	Armstrong, Daiken, Anutone, Diamond, Credence
57.	M.S. Pipe (Railing)	Jindal, Tata, RINL, Prakash Surya, Apolo
58.	M.S. Tubes	SAIL, Tata, Apolo, Prakash Surya, RINL, JSW and JSPL
59.	Multi-coat Synthetic Plaster/ Textured Exterior wall paint	Spectrum, Heritage, Ultratech, Asian Paints, Berger Paints India Ltd.
60.	PL.AL.PL. Pipes	Kitech, Vectus, Jindal
61.	Polycarbonate Sheet	Bayer, Macrolux, Danpalon, DPI Daylights, Fibreways
62.	Polysulphide / Silicon Sealant	Pidilite, Fosroc, Tuffseal, Berger Paints India Ltd.
63.	POP (Plaster of paris)	JK-Laxmi, Sriram Nirman, Sakarni
64.	PPR Pipes	SFMC, SAFE, Poiner Industries, Vectus
65.	Precast CC interlocking Tiles	Hindustan, Paver India, KK, Dalal, Unistone
66.	Pre-coated Profile Sheet	Tata, Bhushan (Jindal), National, Jindal
67.	Pre-laminated Particle Board	Ecoboard, Action-Tesa, Duro, Century Ply, Greenlam
68.	Pressed steel door frame	M/s Engineers & Fabricator, Raipur, M/s J.K. Enterprises, Jaipur, M/s Jangid Engineering Works, Jaipur, M/s Swastik Super Industries, Mohali, M/s SKS Steel Industries, New Delhi.
69.	PTMT Water supply fittings	Prayag, Polytuff, Estylo, Plasto, Shakti
70.	PVC Cistern	Steelbird, Jindal, Prayag, Commander, Shakti, Jaquar, Hindware
71.	PVC Connection Pipe	Supreme, Prince, Finolex
72.	PVC Rain Water Pipe & Fitting (SWR) Pipes	Finolex, Kisan, Kasta, Supreme, Astral, Prince, Vectus
73.	PVC Shutter	Polygreen, Rajshri, Plastogreen, Sintex
74.	PVC Water storage Tank (Only ISI)	VECTUS, Water well, Plasto, Sintex, Gangotri
75.	Ready Mix Concrete (RMC)	ACC, L&T, Grasim, Ultratech, RMC Ind, Supermax
76.	Ready Mix Plaster	Ready Plast (Ultratech), Silico Plast, Perma Plast, Insta Plast
77.	Road Safety Products	Shakti or equivalent
78.	Rust Remover	Perma, Sunanda, Dr. Fixit, Fosroc, Sika
79.	SBR Polymer	Perma, Sika, Roff Bond, Fosroc
80.	Sluice Valve	Kirloskar, Venus, Kalpana, SANT, KARTAR, Zoloto
81.	Solid PVC frames and shutters	Polygreen, Rajshri, Plastogreen, Sintex
82.	Stainless Steel	Jindal, Salem or equivalent
83.	Stainless steel Sink with or without Draining board.	Nirali, Hindware, Frankee, Neelkanth, Jaquar, Prayag
84.	Stainless steel Door/Window fittings & Fixtures	Dorset, Prayag , Dorma, Ozone, Hettich, Kich, Geze
85.	Structural steel section	TATA, SAIL, RINL, JSW Steel Ltd., Jindal Steel & Power Ltd. (JSPL)
86.	Super plasticizer / admixture	Sika, Fosroc, Chouksey Chemicals, BASF, Asian Paints, Berger Paints India Ltd.
87.	Tactile	Somany, Johnson, Dura, Dalal & NITCO
88.	Tensile Fabric	Bluestone, Encon, Structure Flex
89.	Telescopic Drawer Channels	Godrej, Hetich, Ebco
90.	Tile Adhesive	Ferrous Crete(Ferro-1122), Ardex Endura (Gold Star), PIDILITE (Fevimate XL), WEABR(Saint-Gobin) Sika, Thermoshield, Asian Paints, Berger Paints India Ltd., Ultratech (tile-fixe)
91.	Towel Ring/Towel Rod/Towel Rack	Marc, Jaquar, Kohler, Grohe, Hindware, Prayag
92.	Tubular Seallar Window/ M.S. Tubular Window	M/s Engineers & Fabricator, Raipur, M/s J.K. Enterprises, Jaipur, M/s Swastik Super Industries, Mohali (Punjab) M/s Jangid Engg. Jaipur


93.	UPVC Pipes & Fittings	Astral, Flowguard, Ashirvad, Prince, Supreme, Finolex, VECTUS, Prayag
94.	Urinal, Washbasin, Orrisa Pattern W.C., Wall mounted European W.C. Seat with Cistern	Hindware, Parryware, Jaquar, Cera, Kohler, Grohe
95.	Vitrified Tile, Rectified Tile	Johnson, Marbonite, Somany, Kajaria, NITCO, RAK
96.	Wall Putty	JK, BIRLA, SARAPUTTY, Asian Paints, Berger Paints India Ltd
97.	Waste Pipe	Kamal, Viking, Jaquar
98.	Water Proofing Compound (Liquid)	Pidilite, Cico, Impermo, Fosroc, BASF, Ardex Endura, Sika, Asian Paints, Berger Home Shield.
99.	Water Proofing membrane- PU based	Asian Paints, Berger Home Shield or equivalent
100.	White Cement	JK White, Birla White, Grasim
101.	Wire Meshdoor	A-1 Teak, Century, Greenply, M.P. Wood, Durian
102.	Wooden Frames	A-1 Teak, Century, Greenply, M.P. Wood, Durian
103.	Wooden Flooring	Armstrong, Squarefeet, Action Tesa, Vista
104.	Wood polymer composite (WPC) Door frames and shutters	Sintex, Rajshri, Plastiwood, Alstone, Polygreen
105.	UPVC Windows	Fenesta, Aluplast, Kommerling, Duraplast
106.	Metal Fire Check Doors	Shakthi Hormann, Steeltech, MPP, ASES(Agni Suraksha) & Navair
107.	Non-Metallic Fire Check Doors	Tata Pravesh, Promat, Godrej, Shakthi Hormann, ASES(Agni Suraksha) & Navair
108.	Auditorium Related Material	
109.	Fibre Glass Acoustical Suspended Ceiling	Knauf, Armstrong, Himalayan, Acoustic Hunter Douglas
110.	Woven Vinyl Carpet	Vibrant Floors, Nox, 2Tec2
111.	Acoustic wall panel	Knauf, Armstrong, Himalayan, Acoustic Hunter Douglas
112.	Channelled Perforated Wall Panels	Knauf, Armstrong, Himalayan, Acoustic Hunter Douglas
113.	Auditorium Seating PU Padded	Piero, Godrej, Mapeloak

* Paver blocks produced at site under controlled condition may also be allowed after approval of Engineer-in-charge

Note : 1) In case approved make for any material/item is not specified in the Tender, the decision of finalizing a particular brand shall rest with Incharge, EMS, CIAE ,Bhopal or his successor there off.

2) In case of non-availability of a particular material/item from specified manufacturers/makes, the decision of Incharge, EMS, CIAE ,Bhopal or his successor there off in selection of alternate manufacture/ make is final.

Incharge, EMS


24.1.25

